Bruhat Bangalore Mahanagara Palike

Office of the Executive Engineer,SWD-Dasarahalli Zone,BBMP, 9th Floor
Jayanagara Shopping Complex4th Block, Jayanagar Bengaluru 560011

No:EE/SWD/DHZ /Tend/02/2024-25 Date: 13.03.2025

ADDENDUM-1

Project Name : **Construction of Flood Protection Structures to SWD including RCC Retaining Walls, Water Retention Structures, Nature Based solutions structures / Bridges and Culverts Under Karnataka Water Security and Resilience Programme(KWSRP) with externally funded Project(World Bank in Dasarahalli zone Package -1.**

Ref : 1. Tender Notification NO: EE/SWD/DHZ/TEND/02/2024-25, Dt: 10/03/2025.
2. Tender Number: BBMP/2024-25/CN/WORK_INDENT6818

******

With respect to above subject, following Addendum to the above tender work is issued to be read has below.

Sl No	Section of Tender	Clause / Item No	As published in KPPP BOQ	As Amended & to be read as
1	BOQ	Code 09	Ready Mix Concrete (RMC) with Cement & Cementitious Materials Providing and laying in position Ready Mixed or Batch Mixed concrete as per IS 10262 mix design procedure for Cement Concrete works in all types of Structures other than Road works, using coarse aggregate and fine aggregate derived from natural sources, Ordinary Portland Cement (OPC) @ 75% & GGBS @ 25% proportion, admixtures to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; **but excluding the cost of centering, shuttering, finishing and reinforcement** as per direction of the Engineer-in-charge RMC M25 Grade (Open Foundation) and as per the direction of Engineer in charge	Ready Mix Concrete (RMC) with Cement & Cementitious Materials Providing and laying in position Ready Mixed or Batch Mixed concrete as per IS 10262 mix design procedure for Cement Concrete works in all types of Structures other than Road works, using coarse aggregate and fine aggregate derived from natural sources, Ordinary Portland Cement (OPC) @ 75% & GGBS @ 25% proportion, admixtures to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; **Including the cost of centering, shuttering, finishing and excluding the cost of reinforcement** as per direction of the Engineer-in-charge RMC M25 Grade (Open Foundation) and as per the direction of Engineer in charge
2	BOQ	Code 10	Ready Mix Concrete (RMC) with Cement & Cementitious Materials Providing and laying in position Ready Mixed or Batch Mixed concrete as per IS 10262 mix design procedure for Cement Concrete works in all types of Structures other than Road works, using coarse aggregate and fine aggregate derived from natural sources, Ordinary Portland Cement (OPC) @ 75% & GGBS @ 25% proportion, admixtures to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for	Ready Mix Concrete (RMC) with Cement & Cementitious Materials Providing and laying in position Ready Mixed or Batch Mixed concrete as per IS 10262 mix design procedure for Cement Concrete works in all types of Structures other than Road works, using coarse aggregate and fine aggregate derived from natural sources, Ordinary Portland Cement (OPC) @ 75% & GGBS @ 25% proportion, admixtures to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying,

Scanned with OKEN Scanner

Sl No	Section of Tender	Clause / Item No	As published in KPPP BOQ	As Amended & to be read as
			all leads; **but excluding the cost of centering, shuttering, finishing and reinforcement** as per direction of the Engineer-in-charge RMC M25 Grade (Sub Structure) with all lead & lift as per direction of the Engineer-in-charge	curing, carriage for all leads; **Including the cost of centering, shuttering, finishing and excluding the cost of reinforcement** as per direction of the Engineer-in-charge RMC M25 Grade (Sub Structure) with all lead & lift as per direction of the Engineer-in-charge
3	BOQ	Code 11	Ready Mix Concrete (RMC) with Cement & Cementitious Materials Providing and laying in position Ready Mixed or Batch Mixed concrete as per IS 10262 mix design procedure for Cement Concrete works in all types of Structures other than Road works, using coarse aggregate and fine aggregate derived from natural sources, Ordinary Portland Cement (OPC) @ 75% & GGBS @ 25% proportion, admixtures to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; **but excluding the cost of centering, shuttering, finishing and reinforcement** as per direction of the Engineer-in-charge RMC M30 Grade (Open Foundation) with all lead & lift as per direction of the Engineer-in-charge	Ready Mix Concrete (RMC) with Cement & Cementitious Materials Providing and laying in position Ready Mixed or Batch Mixed concrete as per IS 10262 mix design procedure for Cement Concrete works in all types of Structures other than Road works, using coarse aggregate and fine aggregate derived from natural sources, Ordinary Portland Cement (OPC) @ 75% & GGBS @ 25% proportion, admixtures to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; **Including the cost of centering, shuttering, finishing and excluding the cost of reinforcement** as per direction of the Engineer-in-charge RMC M30 Grade (Open Foundation) with all lead & lift as per direction of the Engineer-in-charge
4	BOQ	Code 12	Ready Mix Concrete (RMC) with Cement & Cementitious Materials Providing and laying in position Ready Mixed or Batch Mixed concrete as per IS 10262 mix design procedure for Cement Concrete works in all types of Structures other than Road works, using coarse aggregate and fine aggregate derived from natural sources, Ordinary Portland Cement (OPC) @ 75% & GGBS @ 25% proportion, admixtures to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; **but excluding the cost of centering, shuttering, finishing and reinforcement** as per direction of the Engineer-in-charge RMC M30 Grade (Sub Structure) with all lead & lift as per direction of the Engineer-in-charge	Ready Mix Concrete (RMC) with Cement & Cementitious Materials Providing and laying in position Ready Mixed or Batch Mixed concrete as per IS 10262 mix design procedure for Cement Concrete works in all types of Structures other than Road works, using coarse aggregate and fine aggregate derived from natural sources, Ordinary Portland Cement (OPC) @ 75% & GGBS @ 25% proportion, admixtures to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; **Including the cost of centering, shuttering, finishing and excluding the cost of reinforcement** as per direction of the Engineer-in-charge RMC M30 Grade (Sub Structure) with all lead & lift as per direction of the Engineer-in-charge
5	BOQ	Code 13	Ready Mix Concrete (RMC) with Cement & Cementitious Materials Providing and laying in position Ready Mixed or Batch Mixed concrete as per IS 10262 mix design procedure for Cement Concrete works in all types of	Ready Mix Concrete (RMC) with Cement & Cementitious Materials Providing and laying in position Ready Mixed or Batch Mixed concrete as per IS 10262 mix design procedure for Cement Concrete works in all types of

Scanned with OKEN Scanner

Sl No	Section of Tender	Clause / Item No	As published in KPPP BOQ	As Amended & to be read as
			Structures other than Road works, using coarse aggregate and fine aggregate derived from natural sources, Ordinary Portland Cement (OPC) @ 75% & GGBS @ 25% proportion, admixtures to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; **but excluding the cost of centering, shuttering, finishing and reinforcement** as per direction of the Engineer-in-charge RMC M30 Grade (Solid Slab Super Structure) with all lead & lift as per direction of the Engineer-in-charge	Structures other than Road works, using coarse aggregate and fine aggregate derived from natural sources, Ordinary Portland Cement (OPC) @ 75% & GGBS @ 25% proportion, admixtures to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; **Including the cost of centering, shuttering, finishing and excluding the cost of reinforcement** as per direction of the Engineer-in-charge RMC M30 Grade (Solid Slab Super Structure) with all lead & lift as per direction of the Engineer-in-charge

All other terms & conditions remain unchanged.

13/3/25

Executive Engineer
SWD-Dasarahalli Zone
Bruhat Bengaluru Mahanagara Palike

Copy submitted to:

1. Chief Engineer (SWD) for kind information.
2. Superintending Engineer (SWD) for kind information.
3. Office Copy.

Scanned with OKEN Scanner